TOWN MUNICIPAL COUNCIL, MANDYA.

Tender Notification dated 13th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the President, Mandya Town Municipality, Mandya, up to 3 P.M. on 15th April 1940, for constructing a Bus Stand in Mandya Town. An approximate estimate of quantities is given below. These quantities are only approximate. The work should be completed by the end of June 1940.

2. The plans, detailed estimates and conditions may be seen at the Town Municipal Office at Mandya, on all working days between 11 A.M. and 5 P.M.

3. Tenders should be submitted in the prescribed form in the Public Works Department and should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for earnest money of Rs. 250 paid to Treasury to the head of deposit and be superscribed "Tender for construction of a Bus Stand at Mandya" in default of which the tender will be rejected.

5. The final acceptance of the tender will rest with the Municipal Council, Mandya, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Town Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department, or those fixed by the Municipal Council after working out date.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Municipal Council will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against cash item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The quality of the materials used and the work should be as per specification.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills of the contractor and the same repaid after the due fulfilment of the contract.

Abstract estimate for constructing a Bus Stand—Plan I.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavating for foundations and filling in basement with watering and consolidating.	Cyd.	0 4 0	66	
2	Burnt stone jelly concrete in lime mortar 1 : 2 : 4 for foundations with tamping in layers not more than 6" thick.	C.ft.	0 3 6	602	
3	Burnt size stone in mud for foundations with bond stones 6 ft. apart.	,,	0 3 6	823	
4	Burnt size stone in mud for basement with bond stone 6 ft. apart including all quoins neatly dressed 2" wide.	,,	0 4 0	169	
5	Burnt stone slabs 6" thick for basement and step including two lines dressing on exposed faces and one line dressing on all other faces.	Sq. ft.	0 5 0	396	
6	Burnt brick in mud superstructure ...	C.ft.	0 3 0	894	
7	Burnt brick in lime mortar superstructure.	,,	0 4 0	132	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
8	Burnt stone slabs 6" thick one line dressed on all exposed faces for lintels of doors, sills and lintels of windows and ventilators and stone plates below roof level.	Sq. ft.	0 5 0	130	
9	Reinforced cement concrete 1 : 2 : 4, pillars 10" dia. 10 ft. high with grooves cut at top and bottom as per design including cement plastering ½ inch thick.	C.ft.	3 8 0	109	
10	Rolled steel girders as per B. S. S. including lifting and hoisting and boxing with cement mortar and terraced brick reinforced with galvanised steel-tex tied from above with one coat of anti-corrosive painting with mouldings as per design.	Cwt.	14 0 0	19·15	
11	Reinforced cement concrete pre-cast seat as per design, 32' length, 3¾ ft. wide, 3 ft. high with cement plastering, etc., complete.	Sq. ft.	3 8 0	120	
12	Reinforced cement concrete chejja 3 ft. projection from the wall, 3" thick, 11/8 ft. anchorage into the wall over windows and doors of the restaurant as lintels.	,,	0 10 0	70	
13	Teakwood doors 4"×5" frame with 1¼" thick panelled shutters with iron hinges, hooks and stoppers, including brass hasps, staples and handles, etc., complete including two coats of approved varnish with teakwood counters fixed to each door as per design.	,,	2 0 0	85	
14	Teakwood door 3"×4½" frame with 1¼" thick panelled shutters with usual iron fittings including two coats of approved paint.	,,	1 12 0	26	
15	Teakwood windows 3"×4" frame with 1" thick panelled shutters in four halves to open outside with steel parliamentary hinges, hooks and brass rings 2" dia. etc., including two coats of approved paint.	,,	2 0 0	30	
16	Teakwood ventilators 3"x4" frame with glaxed shutters in two halves including usual iron fittings and two coats of approved paint.	,,	1 8 0	9	
17	Roofing with reinforced cement concrete terrace with sufficient reinforcement to take a superload of 60 lb. per sq. ft. with R. C. chejja projected from roof all round the building 4 ft. width having 3 inches thick at the end including chunam plastering on both sides of the terrace.	Sqr.	70 0 0	12·14	
18	Flooring with cement concrete 1: 2: 4 1¼" thick on a bed of 4½" thick lime concrete, with topping of red cement mortar 3/8" thick, finished smooth and cut to tile pattern.	,,	20 0 0	12·52	

Sl. No.	Items of work.	Unit	Rate	Quantity	Cost
			Rs. a. p.		
19	Flooring with burnt stone slabs 3" thick, to surface and joints one line dressed on a bed of 3" thick, lime concrete with cement pointing to the slabs.	Sqr.	25 0 0	0·50	
20	Plastering the walls of lavatories and Restaurant with chunam plaster.	,,	3 0 0	24·45	
21	Pointing the basement with cement and lining nicely.	,,	2 8 0	4·45	
22	Whitewashing, two coats ...	,,	0 4 0	48·26	
23	R. C. louvred panels between pillars of Hall 15" depth, each louvre being 2' slant depth and ½ inch thick as per design.	Sq.ft.	1 8 0	98	
24	Cement perforated ventilators as per design over doors and windows of Restaurant.	,,	1 0 0	5	
25	Notice Board plastered with ½" thick cement with border as per design.	,,	..	28	
26	Providing moulding 6" thick as per design alround the Restaurant at the roof level.	R.ft.	0 6 0	55	
27	Trellis work with creepers at the rear having 2" dia. galvanized vertical pipes fixed in lime concrete and horizontal pipes 2 inches dia. fixed to verticals both at top and bottom for frames and the rectangular compartments to be fitted with galvanized wire netting with 3" square opening, etc., complete as per design.	Sq. ft.	0 4 0	427	
28	Paving the rear open yard with 4" thick burnt stone slabs over a gravel bed of 6" thick and the top surface one line dressed with cement pointing.	,,	0 7 0	403	
29	Levelling ground and clearing site ..	Lumpsum	...	30	
30	Unforeseen charges ...	,,	...	75	
	C. Total Cost ...	...	..	...	
	Contingencies at 5 per cent nearly ...	...	...	...	
	Architect's charges at 1½ per cent	...	...	...	
	Grand Total ..	...	...	...	

B. BEERAPPA,
President.

HASSAN DISTRICT.

Notification No. Ml. C. 2477—39, *dated* 19*th March* 1940.

In partial modification of Notification No. M. L. C. 2477—39, dated 7th March 1940, published at page 195, Part III—3 of *Mysore Gazette*, dated 14th March 1940, fixing several places as polling centres in connection with the ensuing elections to the Hassan District Board, it is hereby notified for the information of the public that in respect of the following